

FreshFlow Beverages Pvt. Ltd.

FreshFlow Bottling Plant - Pune Production Facility
FSSAI: 10012022000345 | ISO 22000:2018 / ISO 14001:2015

STANDARD OPERATING PROCEDURE

Quality Inspection Procedure for Labeling Line 56

Department: Labeling

Document Number: SOP-056
Revision: Rev 2.3
Classification: CONFIDENTIAL - INTERNAL USE ONLY
Prepared by: Engineering / QA Department
Approved by: Plant Manager

Document Control Information

Parameter	Value
SOP Number	SOP-056
Title	Quality Inspection Procedure for Labeling Line 56
Department	Labeling
Plant	FreshFlow Bottling Plant - Pune Production Facility
Prepared By	Employee 8
Reviewed By	Farah Shaikh
Approved By	Rajesh Kulkarni - Plant Manager
Issue Date	2022-04-06
Next Review Date	2027-03-11
Revision	Rev 1.0

1. Purpose

Apply labels correctly and consistently so all bottles carry accurate product information complying with FSSAI labeling regulations and FreshFlow brand standards.

2. Scope

Labeling department operators, quality inspectors, and maintenance technicians.

3. Prerequisites and Requirements

3.1 Training Requirements

- Labeling machine operation training
- Vision system calibration training

3.2 Tools and Materials Required

- Calibrated instruments as listed in the plant calibration schedule.
- Appropriate PPE as specified in Section 4.
- Completed permit-to-work (if required for maintenance activities).
- Access to relevant equipment manual and P&ID drawings.
- CMMS access to create and close work orders.

4. Health, Safety and Environmental Requirements

! WARNING

This SOP must not be carried out without appropriate PPE and, where required, a valid Permit to Work (SOP-SAF-006). If in doubt about safety, STOP and consult the Safety Officer (EMP009 / EMP017).

4.1 Identified Hazards

- Hot melt glue (140-160°C) - thermal burn risk if contacted
- Solvents in label adhesive - ventilation required
- Cutting tools for label splicing - laceration risk

4.2 Emergency Response

In case of any emergency during this procedure: Press the nearest Emergency Stop, alert personnel in the vicinity, call the Safety Officer and Shift Supervisor. Refer to the Emergency Response Plan (SOP-SAF-004) and site evacuation procedure.

5. Detailed Procedure

5.1 Pre-Task Verification

1. Confirm the relevant equipment is available and no conflicting activities are planned.
2. Check shift handover log for any outstanding issues with this equipment.
3. Verify all required materials, tools, and chemicals are available and correctly labelled.
4. Obtain all required permits (PTW, hot work, confined space as applicable).
5. Brief all involved personnel on this SOP before starting.

5.2 Main Procedure

1. Isolate and LOTO the equipment per SOP-SAF-002. Verify zero energy state.
2. Allow equipment to cool to ambient temperature before touching internal parts.
3. Disassemble relevant sub-assembly according to the equipment manual section 6.
4. Inspect all removed parts. Photograph any damaged or worn components.
5. Clean the housing and contact surfaces. Remove all old gasket material.
6. Install new parts using food-grade lubricants where applicable. Do not over-torque fasteners.
7. Reassemble in reverse order. Verify all fasteners are tightened to specified torques.
8. Remove LOTO and test equipment at low speed/load before returning to production.
9. Verify key parameters (pressure, temperature, vibration) after restart.
10. Record the work in CMMS with parts used, cost, and technician details.