

# FreshFlow Beverages Pvt. Ltd.

FreshFlow Bottling Plant - Pune Production Facility  
FSSAI: 10012022000345 | ISO 22000:2018 / ISO 14001:2015

## RCA REPORT

### Root Cause Analysis (RCA)

Subject: Pump cavitation in water transfer line

**Equipment ID: CH101**

|                                                  |
|--------------------------------------------------|
| Document Number: RCA-035                         |
| Revision: Final                                  |
| Classification: CONFIDENTIAL - INTERNAL USE ONLY |
| Prepared by: Engineering / QA Department         |
| Approved by: Plant Manager                       |

## 1. RCA Information

### 1.1 Overview

| Parameter                   | Value                             |
|-----------------------------|-----------------------------------|
| RCA ID                      | RCA-035                           |
| Date of RCA                 | 2023-12-05                        |
| Reference Event/Incident ID | FE-035                            |
| Equipment / Asset           | CH101 - CH101 Chiller             |
| Department                  | Utilities                         |
| Facilitator                 | Arjun Nair (Maintenance Engineer) |
| Methodology Used            | Fishbone (Ishikawa)               |

## 2. Problem Statement

The following issue occurred leading to a disruption in operations, quality, or safety: Pump cavitation in water transfer line. The immediate impact required corrective action to stabilize the process.

## 3. 5-Whys Analysis

The cross-functional team conducted a 5-Whys analysis to drill down to the systemic root cause.

| Question                    | Answer                                                  |
|-----------------------------|---------------------------------------------------------|
| Why did the problem happen? | Pump cavitation in water transfer line                  |
| Why?                        | Because of component/process failure.                   |
| Why did it fail?            | Because it reached its operational limit / was out of s |
| Why was it out of spec?     | Because: Blocked water filter reduced suction pressure  |
| Why? (Root Cause)           | Systemic gap in maintenance plan or operational procedu |

## 4. Identified Root Cause

Blocked water filter reduced suction pressure

This has been classified as a systemic failure requiring permanent corrective action.

## 5. Corrective and Preventive Actions (CAPA)

| Action Items                                            | Owner      | Target Date |
|---------------------------------------------------------|------------|-------------|
| Flush water line, replace filter cartridge, verify suct | Arjun Nair | 2023-12-12  |
| Update Equipment Manual and PM Schedule                 | Employee 5 | 2023-12-19  |
| Train operators on new procedure                        | Employee 8 | 2023-12-26  |

6. Sign-off

Plant Manager Approval: \_\_\_\_\_

Date: 2023-12-07